



NOTES: **SECTION A-A** **SECTION B-B** **REINFORCEMENT LAYOUT**

1. CONCRETE: 5,000 PSI MINIMUM AFTER 28 DAYS.
2. STEEL REINFORCEMENT SHALL BE #4 REBAR AND MEETS REQUIREMENTS OF ASTM A615 GRADE 60.
3. ANCHOR BOLTS: (4) $\frac{3}{4}$ " DIAMETER X 48" X 3" L-SHAPED GALVANIZED STEEL, EACH WITH (2) HEAVY HEX HEAD NUTS AND (2) ROUND WASHERS. MINIMUM 12" THREAD LENGTH. ALL HARDWARE SHALL CONFORM TO ASTM A36, A563, AND F844, RESPECTIVELY. FABRICATED IN ACCORDANCE WITH ASTM F1554 AND HOT-DIP GALVANIZED PER A153.

ITEM NO.	UTL-NGMS6640LPB	WEIGHT
		2,225 LBS

SHEA CONCRETE PRODUCTS
New England's Premier Precaster
 800-696-7432 (SHEA)
 www.sheaconcrete.com

773 Salem Street-Wilmington, MA 01887
 153 Cranberry Hwy-Rochester, MA 01887
 87 Haverhill Road-Amesbury, MA 01822
 160 Old Turnpike Rd-Nottingham, NH 03840

NATIONAL GRID LIGHT BASE
MS6640-4FT X 8 $\frac{1}{2}$ " BOLT CIRCLE

Page: K5.11
 NGMS6640LPB.dwg 01/01/2013

NPCA
 CERTIFIED PLANT