



**SECTION A-A**

**SECTION B-B**

**REINFORCEMENT LAYOUT**

NOTES:

1. CONCRETE: 5,000 PSI MINIMUM AFTER 28 DAYS.
2. STEEL REINFORCEMENT SHALL BE #4 REBAR AND MEETS REQUIREMENTS OF ASTM A615 GRADE 60.
3. ANCHOR BOLTS: (4)  $\frac{3}{4}$ " DIAMETER X 48" X 3" L-SHAPED GALVANIZED STEEL, EACH WITH (2) HEAVY HEX HEAD NUTS AND (2) ROUND WASHERS. MINIMUM 12" THREAD LENGTH. ALL HARDWARE SHALL CONFORM TO ASTM A36, A563, AND F844, RESPECTIVELY. FABRICATED IN ACCORDANCE WITH ASTM F1554 AND HOT-DIP GALVANIZED PER A153.

WEIGHT

ITEM NO.	UTL-NGMS6642LPB	2,225 LBS
----------	-----------------	-----------



New England's Premier Precaster  
800-696-7432 (SHEA)  
www.sheaconcrete.com

773 Salem Street-Wilmington, MA 153 Cranberry Hwy-Rochester, MA  
87 Haverhill Road-Amesbury, MA 160 Old Turnpike Rd-Nottingham, NH  
Mail to: PO Box 520-Wilmington, MA 01887

Page: K5.13

NGMS6642LPB.dwg

01/01/2013



NATIONAL GRID LIGHT BASE  
MS6642-4FT X 15" BOLT CIRCLE