



NOTES:

1. CONCRETE MINIMUM STRENGTH 4,000 PSI AFTER 28 DAYS.
2. REINFORCEMENT: #5 REBAR.
3. 75 TO 500KVA 3Ø.
4. MEETS PUBLIC SERVICE OF N.H. SPECS.

WEIGHT	
ITEM NO. PSNH500KV12	14,385 LBS
PSNHPIT1	3,100 LBS



New England's Premier Precaster
 800-696-7432 (SHEA)
 www.sheaconcrete.com

**PSNH TRANSFORMER PAD
 75 TO 500 KVA W/CONCRETE PIT**

