


PLAN VIEW



SECTION VIEW

NOTES:

1. CONCRETE: 5,000 PSI MINIMUM AFTER 28 DAYS.
2. DESIGN CONFORMS WITH 310 CMR 15.00 DEP TITLE 5 REGS FOR SEPTIC TANKS.
3. ALL REINFORCEMENT PER ASTM C1227.
4. DESIGNED FOR H-20 LOADING, COVER 1-5 FT.
5. TONGUE AND GROOVE JOINT SEALED WITH BUTYL RESIN. INLET HEIGHT MAY INCREASE SLIGHTLY DUE TO THE BUTYL RESIN USED.
6. TEES AND BAFFLES SOLD SEPARATELY.

GALLONS	A (HEIGHT)	B* (INLET)	C (LIQUID)	WEIGHT (LBS)
3,500	78"	61"	52"	45,970
4,000	86"	69"	60"	48,770
4,500	92"	75"	66"	50,820
5,000	99"	82"	73"	53,210
5,500	106"	89"	80"	55,690
6,000	114"	97"	88"	58,410
6,500	121"	104"	95"	60,900
7,000	128"	111"	102"	63,260
7,500	135"	118"	109"	65,750
8,000	142"	125"	116"	68,100

*SEE NOTE 5



New England's Premier Precaster
 800-696-7432 (SHEA)
 www.sheaconcrete.com

COMMERCIAL LINE TANK
 3500 TO 8000 GALLON

773 Salem Street-Wilmington, MA 153 Cranberry Hwy-Rochester, MA
 87 Haverhill Road-Amesbury, MA 160 Old Turnpike Rd-Nottingham, NH
 Mail to: PO Box 520-Wilmington, MA 01887

Page: 17

ctk8x17.dwg 02/01/2013

