



INLET	D	A	B	W
4"	4'-0"	3'-0"	2'-6"	5"
5"	4'-0" 4'-0"x4'-0"	3'-6" 3'-0"	3'-0" 2'-6"	5" 6"
6"	4'-0" 4'-0"x4'-0" 5'-0"	5'-0" 4'-0" 3'-6"	4'-6" 3'-6" 3'-0"	5" 6" 6"
8"	5'-0" 6'-0" 8'-0"	6'-0" 4'-0" 3'-0"	5'-0" 3'-6" 2'-6"	6" 7" 9"
10"	6'-0" 8'-0"	6'-6" 5'-0"	5'-6" 4'-0"	7" 9"

NOTES:

1. CONCRETE: 4,000 PSI MINIMUM AFTER 28 DAYS.
2. MANHOLE DESIGN SPECIFICATIONS CONFORM TO LATEST ASTM C478 SPEC FOR "PRECAST REINFORCED CONCRETE MANHOLE SECTIONS."
3. BUTYL RESIN SECTION JOINT CONFORMS TO LATEST ASTM C443 SPEC.
4. STEEL REINFORCED COPOLYMER POLYPROPYLENE PLASTIC STEP CONFORMS TO LATEST ASTM C478 SPEC.
5. PIPE NOT SUPPLIED.
6. CONE SECTION AVAILABLE IN 4'-0" I.D. ONLY.
7. FOR INLETS LARGER THAN 10" THE DESIGN AND DIMENSION WILL BE DETERMINED FOR EACH PARTICULAR CASE.



*New England's Premier Precaster*  
 800-696-7432 (SHEA)  
 www.sheaconcrete.com

OIL AND GREASE SEPARATOR

773 Salem Street  
 P.O. Box 520  
 Wilmington, MA 01887

87 Haverhill Road  
 P.O. Box 807  
 Amesbury, MA 01913

160 Old Turnpike Road  
 Nottingham, NH 03290

Page: H1  
 gastrap.dwg

1/13/2005

