



NOTES:

1. CONCRETE: 5,000 PSI MINIMUM AFTER 28 DAYS.
2. REINFORCING REBAR MEETS ASTM A706 GRADE 60, WELDED TO STEEL CONNECTOR PLATES.
3. ALL REINFORCEMENT HOT-DIP GALVANIZED AND EPOXY.
4. DESIGN: FHWA APPROVED POSITIVE CONNECTION. J-J HOOKS IS ACCEPTED BY FHWA AS A CRASH TESTED AND OPERATIONAL DESIGN FOR USE ON ALL FEDERAL AID HIGHWAY PROJECTS.
5. CERTIFIED MASH, TEST LEVEL 3, CRASH TESTED.
6. FOR BOLT DOWN APPLICATION ONLY (2) BOLTS REQUIRED. INCLUDES (2) HILTI BOLT KITS TO BE INSTALLED ON THE TRAFFIC SIDE OF BARRIER.
7. INSTALLATION: BARRIERS ARE SELF-ALIGNING WITH NO LOOSE HARDWARE.

	WEIGHT
ITEM NO. MC-MBDFBD	4,550#



New England's Premier Precaster
800-696-7432 (SHEA)
www.sheaconcrete.com

TEMPORARY BARRIER TYPE F
BOLT DOWN AND J-J HOOK

773 Salem Street-Wilmington, MA 153 Cranberry Hwy-Rochester, MA
87 Haverhill Road-Amesbury, MA 160 Old Turnpike Rd-Nottingham, NH
Mail to: PO Box 520-Wilmington, MA 01887

Page: J4.7-2 02/01/2013

medbar DOT Bolt Down.dwg

