



NOTES:

1. CONCRETE: 5,000 PSI MINIMUM AFTER 28 DAYS.
2. DESIGN CONFORMS WITH 310 CMR 15.00, DEP TITLE 5 REGS, FOR SEPTIC TANKS.
3. ALL REINFORCEMENT PER ASTM A-615
4. DESIGNED H-20 LOADING, 2 TO 5 FEET COVER.
5. TEES AND BAFFLES SOLD SEPARATELY.
6. TONGUE AND GROOVE JOINT SEALED WITH BUTYL RESIN AND BOLTED WITH 3/4" DIA BOLTS.

GALLONS	A (LENGTH)	B (LENGTH)	C (BAFFLE)	WEIGHT
13,000	26'-3"	24'-11"	9'-0"	103,950#
14,000	28'-2"	26'-10"	9'-0"	110,386#
15,000	30'-1"	28'-9"	9'-8"	116,822#
16,000	32'-0"	30'-8"	10'-8"	123,258#
17,000	33'-11"	32'-7"	10'-11"	129,694#
18,000	35'-10"	34'-6"	11'-7"	136,130#
19,000	37'-9"	36'-5"	12'-2"	142,566#
20,000	39'-8"	38'-4"	12'-10"	149,002#
21,000	41'-7"	40'-7"	13'-5"	155,438#
22,000	43'-6"	42'-2"	14'-1"	161,874#
23,000	45'-5"	44'-1"	14'-4"	168,310#
24,000	47'-4"	46'-0"	14'-4"	174,746#



New England's Premier Precaster
 800-696-7432 (SHEA)
 www.sheaconcrete.com

TUNNEL TANK
 13,000 GALLON AND UP

773 Salem Street
 P.O. Box 520
 Wilmington, MA 01887

87 Haverhill Road
 P.O. Box 807
 Amesbury, MA 01913

160 Old Turnpike Road
 Nottingham, NH 03290

