

Boat Ramp Installation

Installation

Blossom Street Boat Ramp
Lynn, MA

Engineer

Bourne Consulting Engineering
Franklin, MA

Site Contractor

Meninno Construction
Lynn, MA



Structure Description

Project consisted of installing twelve Precast Concrete Boat Ramp Panels. Precast Concrete was designed in order to accommodate the tidal conditions. The panels were 6' x 16' and were mounted together using stainless steel brackets embedded in the concrete. The concrete mix was a DOT design using epoxy reinforcement. Shea Concrete was able to manufacture and deliver the panels according to the contractor's schedule.



Comments

The contractor was able to install the precast panels and not be concerned about pouring the boat ramp sections during tidal conditions. This allowed the contractor to work all day even when the tide was approaching the top of the shoring.

87 Haverhill Road
Amesbury, MA 01913

153 Cranberry Highway
Rochester, MA 02770

773 Salem Street
Wilmington, MA 01887

160 Old Turnpike Road
Nottingham, NH 03290

Mail to: PO Box 520 • Wilmington, MA 01887

