

Pump Chamber & Septic Tank Installation

Installation

Lakewood Heights Development
Merrimac, MA

Site Contractor

Busby Construction
Atkinson, NH



Structure Description

Project consisted of installing a Pump Chamber 96" ID x 11VF and two 2500 Gallon Monolithic Commercial Line Tanks used for overflow in case of emergencies. Due to water table and weather conditions the contractor was under time restraints. Shea Concrete was able to manufacture and deliver the customized pump chamber with holding tanks in a timely manner. Shea Concrete Products using their 25 Ton QMC Delivery Truck/Crane was able to set the products in the contractor already prepared excavation, allowing the contractor to quickly backfill after delivery.

Comments

The contractor was able to finish the pump chamber promptly and reduced the cost of maintaining an excavation during high water table and severe weather conditions.

87 Haverhill Road
Amesbury, MA 01913

773 Salem Street
Wilmington, MA 01887

Mail to: PO Box 520 • Wilmington, MA 01887

153 Cranberry Highway
Rochester, MA 02770

160 Old Turnpike Road
Nottingham, NH 03290

